



Breather Membrane

Sheathing Board

Wall Tie

Cavity Tray

Blockwork

Render Finish

Mineral Wool Cavity Closer

Prestressed Concrete Lintel

Weather Seal

Window Frame

Fibre Insulation

**E500 Foam Sprayed  
Between Studs to  
Specified Depth.  
Add Battens if  
Depth of Foam is  
Greater Than Stud  
Depth**

Vapour Control Layer

Plasterboard

Lintel Beams

Spacer

Window Clip

**NEW BUILD  
TIMBER FRAME  
Lintel  
(SECTION)  
TGD L 2008 & 2010**

These drawings are the exclusive property of CPI Foam Ltd. Any reproduction without prior written authority is strictly prohibited. Do not scale drawings. Copyright © 2011



Unit 2c, Charvey Lane Ind Est,  
Rathnew, Co. Wicklow,  
Ireland.  
Tel: 353 (0) 404 66111  
[info@cpifoam.ie](mailto:info@cpifoam.ie)

Issued For: <b>Approval</b>		Title: <b>New Build Timber Frame Lintel TGD L 2008 &amp; 2010</b>	
Scale: <b>NTS</b>	Drawn by: <b>PB</b>	Approved by: <i>KL</i>	Date: <b>20/06/2011</b>
Project: <b>CPI Foam Details</b>		Drawing No. <b>CPI-SD-006</b>	Revision: <b>/</b>